



MIN. STEEL CASING SCHEDULE		
DIP WL SIZE	STEEL CASING SIZE	MINIMUM WALL THICKNESS
4"	10"	0.250"
6"	12"	0.250"
8"	16"	0.250"
10"	18"	0.250"
12"	24"	0.312"
14"	24"	0.312"
15"	26"	0.344"
16"	30"	0.406"
18"	30"	0.406"
20"	36"	0.469"
24"	42"	0.562"
30"	48"	0.562"
36"	54"	0.562"



- NOTES:**
1. THE NEAR EDGE OF THE PIT CAN BE NO CLOSER TO THE EDGE OF THE TRAVELWAY THAN ITS DEPTH BELOW THE SURFACE OF THE TRAVELWAY UNLESS BULKHEADED.
 2. ALL PIPE WITHIN AND TO 5' OUTSIDE THE CASING TO BE D.I.P.
 3. ALL PIPING IN CASING SHALL UTILIZE LOCKING GASKETS SUPPLIED BY THE PIPE MANUFACTURER.

GREER COMMISSION OF PUBLIC WORKS
CASING PIPE
BORE AND JACK DETAIL

APPROVED BY: --		DATE: FEBRUARY 2021	DRAWING NO. WW-20
SCALE: NTS		REVISED: --	