


DROP BOWL  
MOUNTING  
POSITION



INSIDE DROP - PLAN

RELINER® INSIDE DROP BOWL  
SECURED WITH STAINLESS  
STEEL BOLTS

TRIM PIPE TO 2" MAX.  
V NOTCH BOTTOM EDGE


FERNCO FLEXIBLE  
COUPLING OR EQUAL

COMPRESSION  
COUPLING  
MORTAR

RELINER® STAINLESS STEEL  
STRAPS OR EQUAL. SECURE  
TO STRUCTURE WITH 2  
STAINLESS STEEL BOLTS.  
STRAP AT 4' INTERVALS  
(MIN. OF 2)

PVC SEWER PIPE

GLUE FITTING  
BELL & SPIGOT  
SWEEP ELBOW  
EMBEDDED IN  
CONC. AT 45°  
W/ SEWER FLOW



INSIDE DROP CONNECTION

**NOTES:**

- 1) ALL INSIDE DROP CONNECTIONS FOR SERVICES AND COLLECTOR SEWERS SHALL USE THE DROP BOWL AS PRODUCED BY:  
RELINER-DURAN, INC.  
53 MT. ARCHER RD  
LYME, CT 06371  
(860)434-0277 FAX: (860)434-3195
- 2) SECURE DROP PIPE TO MANHOLE WALL WITH RELINER-DURAN, INC. STAINLESS STEEL ADJUSTABLE CLAMPING BRACKETS.
- 3) MINIMUM 5 FT DIAMETER MANHOLE REQUIRED FOR INSIDE DROP CONNECTION.

**GREER COMMISSION OF PUBLIC WORKS**  
INSIDE DROP MANHOLE DETAIL

APPROVED BY: --		DATE: FEBRUARY 2021	DRAWING NO. WW-7
SCALE: NTS		REVISED: --	